



Hinsdale-Brattleboro Bridge Contractor's Perspective

Presented by:
Dustin Littlefield
Reed & Reed, Inc.

Project Overview

\$63.7M Final Contract (+4% from bid)



3+ Year Duration(Sept 2021- Dec 2024)



1,800 LF / 8 Spans / 7 River Piers



1,300 LF Temp Access Trestle

Scope Highlights

Improved Alignment – Avoids “Malfunction Junction”



MSE Walls and VT Rt. 142 Reconstruction



Upgraded Utility Infrastructure



New Boat Ramp for the Town of Hinsdale, NH



Demolition of Existing Buildings

Key Quantities

12,000 LF of 30" x 1" Pipe Pile



Over 12,000 CY of concrete



2,900 tons of Structural Steel




900 tons of Rebar













Heavy Lift Operations – Critical Lifts

- Up to 1,065-ton lifting capacity
- Paired girder lifts
- Challenging river work




















Lessons Learned, Project Challenges & Successes

Utilities

Permits

Right of Way

Coordinating Project Drawings

Project Management & Contract Administration

FRP Drains & Pipe

Closed Drain System

Substructure Piling Challenges

Precast Deck Panels on Curved Girders

The River

Collaboration

Project Completion

Utility Challenges

Issue:


- Relocation not complete ahead of construction
- Utilities within work zones

Impact:

- Delay temp access and critical work
- Increased hazards and inefficiencies







SIDEWALK CURVE INFORMATION

1	PC = 0+32.23	N 26°30'14.5" E
2	PT = 0+72.27	N 37°22'16.3" W
3	PC = 1+45.87	
4	PT = 1+70.42	N 41°24'30.2" E



- Cofferdam install prolonged
- Shifted Temp. Access alignment
- Start of Temporary Access delayed



Takeaway: Negotiate & perform utility moves ahead of mobilization

Permitting Challenges

- Are permits current?
- “Dewatering” requirements fit application?
- Contaminated Soils



Takeaway: Permit language should reflect site conditions and realistic construction methods


Right of Way: Ensure Agreements Have Timelines and/or Damages

Pier 1 Access

- Barrows & Fisher new fuel infrastructure near complete upon mobilization Sept. '21
- Special Provisions allow access by April 1, 2022
- Completion, Commissioning & Demo dragged on for 18 months following April 1 deadline
- Access granted late October 23, 2023
- Presumably no provisions in VT ROW agreement to address delays
- Substantial schedule & cost risk for Dept.


George's Field Signal

- Slated for removal in contract documents
- No restrictions for when it could be removed by the contractor
- Permission to remove kicked down the road
- Ultimately went to court
- Relocated...Not removed



Coordinate Documents

- Ensure elevations are coordinated between Civil & Bridge plans
- Construction Sequence
- Aesthetics





Project Management & Contract Administration

- Project Manager did not bid the project
- Subcontract Administration
- Timely Lower Tier Subcontractor submission

Fiberglass Drains & Pipe

- Development of Special Provisions
- Testing requirements
- Single Source Vendor
- Overpriced
- Variance of Special Provision
- Constructability



Closed Drain System

Original Design:



- Multi-component system discharging to river

What Changed:

- Redesigned to eliminate underground components
- Fabrication already complete

Impact:



- Added cost
- Avoided potential environmental impact





Substructure Pile Challenges

- Heavy 1" Wall Pipe – Spliced in Place
- 4 hrs. per splice with 7 passes
- Battered all Directions – Phased Installation
- Cleanout to 80' – Multiple Methods



Battered Pile Conflicts



Multiple Cleanout Methods: Auger w/ Flighting, Air Lift, Soilmec Auger

Precast Deck Panels – Curved Girders



What Happened:

- Panel movement due to girder behavior (thermal effects)
- Large blocking heights increased instability

Impact:

- Inefficient Installation
- Increased Safety Risk
- Added Cost

Resolution:

- Changed Blocking Foam
- Secured Panels
- Shorter Grout Pours

Takeaway:

- Panel stability & constructability considerations for curved girders



Challenging River Variables – Seal Event

Dewatered
5/15/23

What Happened:

- High Water During Pour
- Abrupt Flow Changes After Pour
- Unexpected Elev. Gain ~ + 3'

Observations:

- Seal “Floated”
- Perfectly Flat...That’s Odd!
- Seal Sounded Hollow & Conc. Soft
- Water Percolating thru Seal





CSL Testing
5/31/23

Response:

- CSL Testing & Coring
- Engineering Review for Stability
- Conservative restart to avoid failure

Seal Cores 7/27/23




- Footer Pour Started 8/24/23...
- Bubbles Observed Downstream & Pour Stopped



- Resumed Balance of Pour 8/30/23
- Finished 4 Months After Seal Poured

Flooding July '23...Lots of Debris & Some Boats from The Marina!!!



Takeaway: River conditions present high uncertainty



Collaboration Enabled Schedule Recovery

Pier 1 delays brought Design & Construction teams together

Aligned ideas to adjust sequencing & advance work

Precast panels extended to VT & accelerated

Deck pours re-sequenced for efficiency

Parallel work activities approved

December 2021



February 2022



June 2022



September 2022



December 2022



February 2023



May 2023



July 2023



November 2023



February 2024



May 2024



July 2024



October 2024



December 4, 2024 – Opening Day!




June 2025



Project Completion – Successful Delivery!!!

- Multiple major challenges overcome
- Delivered bridge opening 5 weeks beyond original completion date
- Special Thanks to:
 - NHDOT: Mark Moran, Jared Hansen, Charlie Lawrence (John Turner Consulting), Steve Lowe, Jeremy Guyette, Deidra Benjamin, Nickie Hunter, Tim Chapman, Bill Saffian, and countless other support staff
 - VTRANS: Gary Laroche and the VTRANS team
 - VHB: Kevin Daigle and staff
 - McFarland Johnson: Sam White and staff
 - Major Sub's & Suppliers: Bazin Brothers, All States, CWS Fence, East Coast Signal, Carroll Concrete, Casco Bay Steel, J.P. Carrara Precast, Rebars & Mesh, Skyline Steel



Questions?